

1030224

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-21,772-00-00

SW, SEC. 16, T 31 S, R 15 W/K

450 feet from N/S section line

2040 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8653

Lease Name Bray Well # 16-1A

Operator: Petroleum Technologies, Inc.

County Barber

Name & Address 4005 East Kellogg

Well Total Depth 4904 159.38 feet

Wichita, KS 67218

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1010

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Aldebaran Drilling Company License Number 5829

Address 453 South Webb Road # 100, Wichita, KS 67207

Company to plug at: Hour: noon Day: 6 Month: March Year: 19 84

Plugging proposal received from Steve Wright

(company name) Petroleum Technologies, Inc. (phone) 316-687-9963

were: 10 3/4" set at 160' 8 5/8" set at 1010' with top of cement at 730'

Attempt to recover 8 5/8" at 730' failed. Attempt to squeeze loss circulation zone at

730'. with 25 sx hot cement. Run in hole at 700' with drill pipe. Pump 20 sx hulls,

and 25 sx cement. Cut surface pipe at 391'. Pulled 245,000# and broke collar at landing

joint. Fill 8 5/8" from 391' to surface with 175' sx cement. 3-6-84

Plugging Proposal Received by Steve Wright  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:00 pm Day: 10 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 7-10-84 - Squeeze annulus with 50 sx cement and shut in with 50#.

Circulate rat hole with 10 sx cement

Circulate mouse hole with 10 sx cement

RECEIVED  
STATE CORPORATION COMMISSION

JUL 11 1984

Bob Tarbutton observed the plugging in March

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: J. H. Metz observed the plugging in July.

(If additional description is necessary, use BACK of this form.)

(old) observe this plugging.

INVOICED

DATE 7-18-84

Signed Steve Wright  
(TECHNICIAN)

INV. NO. 2564

7-10 AUG 3 1984