

To: 1 040617 1-30
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6006

Operator: Molz Oil Company
Name: RR 2, Box 34
Address: Kiowa, KS 67070

API NUMBER 13- 007-21,698-0000 1672
C SE SE, SEC. 2, T. 32 S, R. 11 W/EX

660 feet from S section line

660 feet from E section line

Lease Name Ricke Well # 1

County Barber 122.85

Well Total Depth 3780 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 367

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:45 a.m. Day: 30 Month: 1 Year: 19 92

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 3767' w/125 sx cement, Open hole 3767-80'

1st plug sand back to 3610' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:45 a.m. Day: 30 Month: 1 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 3610' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 110 sx cement.

Maximum pressure 300 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2950' of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED
I (and/or XXXXXX) observe this plugging.

DATE 2-12-92

INV. NO. 34522

Signed [Signature] (TECHNICIAN)