

To: 1 071057  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4-23 API NUMBER 15- 165-21,196-0000  
NW SE SE, SEC. 33, T. 19 S, R. 16 W/E

TECHNICIAN'S PLUGGING REPORT  
Operator License # 6563  
Operator: Double "B" Oil Inc.  
Name & Address: 155 N. Market, Suite 710  
Wichita, KS 67202

990 feet from S section line  
990 feet from E section line  
Lease Name Oetken Well # 5  
County Rush  
Well Total Depth 3748 121.81 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1083

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:05 p.m. Day: 23 Month: 4 Year: 19 92

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 3738' w/100 sx cement, Open hole 3738-48'

1st plug sand back to 3685' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1 p.m. Day: 23 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 3685' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, and 150 sx cement,

Maximum pressure 1000 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3000' of 5 1/2" casing.

(if additional description is necessary, use BACK of this form to observe this plugging.)

INVOICED

DATE 5-12-92

INV. NO. 35207

4-23

Signed Dan Johnson (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 28 1992  
4-28-92  
CONSERVATION DIVISION  
Wichita, Kansas