

1 120362

1-10

137
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-20,838-~~0000~~

SE SW NE, SEC. 33, T 19 S, R 16 W/E

2970 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6462

Lease Name Tammen Well # 39-627

Operator: Kennedy & Mitchell, Inc.

County Rush 123.50

Name & Address

P.O. Box 1045

Well Total Depth 3800 feet

Woodward, OK 73802

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1108

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 316-793-9711

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 10 Month: 1 Year: 1990

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 3800' Perfs at 3782-86'

1st plug sand back to 3730' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 9 sx gel, 75 sx cement, 11 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 10 Month: 1 Year: 1990

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3730' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 9 sx gel, 75 sx cement,

11 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-1050 psi and shut in 850 psi.

JAN 17 1990

1-17-90

CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2117' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
I did/XXXXXX observe this plugging.

DATE JAN 29 1990

Signed Duane Rankin
(TECHNICIAN)

INV. NO. 27213