

11-16-94

RECEIVED  
KANSAS CORPORATION COMMISSION 2-040791

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

FEB 24 1995  
2-24-95  
CONSERVATION DIVISION  
WICHITA, KS

API NUMBER: 15-077-20,252 - 0000

C NW SE, SECTION 16 TOWNSHIP 31 RANGE 8W

OPERATOR LICENSE # 5003 1980 FEET FROM S SECTION LINE  
1980 FEET FROM E SECTION LINE

OPERATOR MCCOY PETROLEUM CORP  
NAME & 3017 N CYPRESS  
ADDRESS WICHITA KS 67226

LEASE NAME: LONG #1  
COUNTY: HARPER  
WELL TOTAL DEPTH: 4408' 143.26

PIPE: 5-1/2" @ 4390'

SURFACE CASING: 8-5/8" @ 208'

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SMD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE  
ADDRESS: ATTICA KS LICENSE: 30346

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: JANA GREEN  
COMPANY NAME: MCCOY PETROLEUM CORP PHONE: 316-

WERE: OH 4399'-4408' - SAND TO 4300' & 2 SX - 35 SX @ 1360'  
- 35 SX @ 900' - CIRC 250'

PLUGGING PROPOSAL RECEIVED BY: STEVE VAN GIESON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( \_\_\_\_\_ ) PART ( X ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 10:30 DAY: 16 MONTH: 11 YEAR: 1994

ACTUAL PLUGGING REPORT:  
CIBP SET @ 4300' & CAPPED W/2 SX CMT - 5-1/2" CSG  
SHOT LOOSE @ 2034' & PULLED TO 1365' & 30 SX CMT SPTD  
- CSG PULLED TO 875' & 30 SX CMT SPTD - CSG PULLED TO  
261' & CMT CIRC TO SURF - REMAINING CSG PULLED & CMT  
TOPPED OFF

REMARKS: ALLIED CMT 60/40 4% GEL

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 2-27-95

Steve Van Gieson  
Steve Van Gieson (AGENT)

INV. NO. 42288