

10-8

2-040748

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-077-20,665-0000

App NE NE SE, SECTION 16 TOWNSHIP 31 RANGE 8W

OPERATOR LICENSE # 5003 2310 FEET FROM S SECTION LINE  
410 FEET FROM E SECTION LINE

OPERATOR McCoy Petroleum Corp.  
NAME & 110 S. Main, #500  
ADDRESS Wichita, KS 67202

**RECEIVED**  
KANSAS CORPORATION COMMISSION

LEASE NAME: Long #2  
COUNTY: Harper  
WELL TOTAL DEPTH: 4388' 142.6'

DEC 30 1992  
12-30-92  
CONSERVATION DIVISION  
WICHITA, KS

CONDUCTOR PIPE: \_\_\_\_\_  
SURFACE CASING: 8-5/8" @ 269'

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SMD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Shawnee Well Service  
ADDRESS: Attica, KS LICENSE: \_\_\_\_\_

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Daryl Hanson  
COMPANY NAME: McCoy Petroleum Corp. PHONE: \_\_\_\_\_

WERE: 4-1/2" @ 4378' - OH 4378-88' - 35 sx 1200' - 35 sx  
800' - circ 300'

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART ( \_\_\_\_\_ ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 1700 DAY: 8 MONTH: 10 YEAR: 1992

ACTUAL PLUGGING REPORT:  
Open hole covered w/CIBP set @ 4330' & capped w/2 sx  
cmt - 4-1/2" recovered from 3226' & pulled to 1188' &  
35 sx cmt spotted - 4-1/2" pulled to 773' & 35 sx cmt  
spotted - 4-1/2" pulled to 300' & cmt circ to surf.

REMARKS: Howco #253988 60/40 4% gel

**INVOICED**

DATE 1-5-93  
INV. NO. 37101

HS  
Steve Van Gieson (AGENT)