

8-26

2-040639 204
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-077-21,154-0000

SW, SECTION 16 TOWNSHIP 31 RANGE 8W

OPERATOR LICENSE # 6581 2420 FEET FROM S SECTION LINE
3990 FEET FROM E SECTION LINE

OPERATOR Bison Energy
NAME & 9320 East Central
ADDRESS Wichita, KS 67206

LEASE NAME: Critzer #C-3
COUNTY: Harper
WELL TOTAL DEPTH: 4422'

143.71

CONDUCTOR PIPE: " @ ' "

SURFACE CASING: 8-5/8" @ 328'

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Shawnee Well Service
ADDRESS: Attica, KS LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: C. J. Lett
COMPANY NAME: Bison Energy PHONE: _____

WERE: 5-1/2" @ 4417' - perfs 4368'-4422' - CIBP 4368' - 35
sx @ 1400' - 35 sx @ 1000' - circ @ 280'.

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 17:00 DAY: 26 MONTH: 8 YEAR: 1991

ACTUAL PLUGGING REPORT:
A CIBP was set @ 4368' & capped with 2 sx cmt - 5-
1/2" was recovered from 2629' & pulled to 1407' where
35 sx cmt spotted - pipe pulled to 991' where 35 sx
spotted - pipe was again pulled to 280' & cmt circ to
surf - remaining pipe pulled from hole & topped w/cmt -
recovered 2629'.

REMARKS: B. J. Services #648765 60/40 poz 2% gel

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 11-8-91

Steve Van Gieson
Steve Van Gieson (AGENT)

INV. NO. 336 K3

FORM CP-2/3
REV. 3/90

8-26

DW