

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21146-00-00
Spot: CSW Sec/Twnshp/Rge: 16-31S-8W
1320 feet from S Section Line, 3960 feet from E Section Line
Lease/Unit Name: CRITSER Well Number: 2C-16
County: HARPER Total Vertical Depth: 4392 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 453 S. WEBB RD. STE 310 PO BOX 78020
WICHITA, KS 67278

Conductor Pipe: Size feet: 8 1/4 2.74
Surface Casing: Size 8.625 feet: 225 135 SX CMT
Production: Size 5.5 feet: 4383 125 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 11/05/2002 10:40 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: DARYL HANSON Company: MCCOY PETROLEUM CORP. Phone: (620) 272-1296

Proposed AS KCC REQUIERS.
Plugging
Method:

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 08 2002
11-8-02
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON
Date/Time Plugging Completed: 11/04/2002 10:40 AM

Witness Type: Plugging Operations Partially Witnessed
KCC Agent: STEVE VANGIESON

Actual Plugging Report:


The perms were covered with sand to 4353 and capped with 5 sks of cement. The casing was recovered from 3045 and pulled to 1300', where 35 sks of cement was spotted. The casing was pulled to 800' where 35 sks of cement was spotted. The casing was pulled to 275', where cement was circulated to surface. The remaining casing was pulled and the cement was topped off. Acid Services Cement Co. 60/40 4% gel'

Remarks:

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE 11-13-02

WV # 2003060806