

1030428

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App. SW NE NE, SEC. 5, T 31 S, R 15 W/K
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,044-00-00

4210 feet from S section line

830 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422

Lease Name Lenkner "B" Well # 1

Operator: Abercrombie Drilling, Inc.
Name & Address: 801 Union Center
Wichita, KS 67202

County Barber (Mississippi) 152.27

Well Total Depth 4685 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 980

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 5:00 am Day: 28 Month: May Year: 19 85

Plugging proposal received from Harvey Moore

(company name) Abercrombie (phone) 316-262-1841

Elevation 1827

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1761'

1st plug at 1020' with 50 sx cement

2nd plug at 390' with 30 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 10:30 am Day: 28 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1020' with 50 sx cement, 2nd plug at 390' with 30

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to

circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 31 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by BJ-Titan

CONSERVATION DIVISION

additional description is necessary, use BACK of this form.)

INVOICED

(check / did not) observe this plugging.

DATE 6-6-85

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 833 / 5-28