

1 060168

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,749 -00-00

SW SE SW, SEC. 16, T 31 S, R 15 W/E  
330 feet from ~~W/S~~ section line

TECHNICIAN'S PLUGGING REPORT

1650 feet from ~~W/E~~ section line

Operator License # 8653

Lease Name Bray Well # 16-1

Operator: Petroleum Technologies, Inc.  
Name & Address 4005 E. Kellogg  
Wichita, KS 67218

County Barber  
Well Total Depth 1700 55.25 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 335

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Aldebaran Drilling License Number 5829

Address 453 S. Webb Road, # 100, Wichita, KS 67207

Company to plug at: Hour: 8:00 am Day: 19 Month: February Year: 19 84

Plugging proposal received from Dorse Foster

(company name) Petroleum Technologies, Inc. (phone) 316-687-9963

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug pumped hole full of heavy mud and got circulation, then pumped 50 sx cement through drill pipe at 380'. Then waited 2 hrs and tagged cement at 360'

2nd plug pumped 15 sx cement at 360', 3rd plug on solid bridge at 40' to surface with 10 sx cement. 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 7:30 pm Day: 19 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug pumped hole full of heavy mud and got circulation, then pumped 50 sx cement through drill pipe at 380'. Waited 2 hours and tagged cement at 360'

2nd plug pumped 15 sx cement at 360', 3rd plug on solid bridge at 40' to surface with 10 sx cement. 5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 22 1984

Remarks: Used common sack cement 4% cc 6% gel by Sun Cementing CONSERVATION DIVISION  
(If additional description is necessary, use BACK of this Wichita, Kansas)

INVOICED (check if did not) observe this plugging.

Signed Paul A. Luthi  
(TECHNICIAN)

DATE 2-23-84

INV. NO. 0349 2-19