

1052268
TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
WICHITA STATE OFFICE BLDG., 130 S. MARKET
WICHITA, KANSAS 67202
TECHNICIAN'S PLUGGING REPORT
OPERATOR LICENSE # 31980
OPERATOR: LOTUS OPERATING CO. L.L.C.
NAME AND ADDRESS 107 N. MARKET, SUITE 416 WICHITA, KS 67202
ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A X

6-18

API NUMBER 15-007-22,568-00-00
E/2 W/2 NE SEC. 33, T 31 S, R 15 W
CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM NORTH SECTION LINE
WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM EAST SECTION LINE
LEASE NAME ALEXANDER WELL # 1
COUNTY BARBER 161.24
WELL TOTAL DEPTH 4961' FEET
CONDUCTOR PIPE: SIZE 10 3/4" FEET 206
SURFACE CASING: SIZE 8 5/8" FEET 1127'
OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR DUKE DRILLING CO. INC. LICENSE NUMBER 5929
ADDRESS 310 W. CENTRAL SUITE 202, WICHITA, KS 67202

COMPANY TO PLUG AT: HOUR: 4:00 PM DAY: 18 MONTH: JUNE YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM JOHN ARMBRUSTER
(COMPANY NAME) DUKE DRILLING COMPANY (PHONE) 316-267-1331

WERE: TO FILL HOLE WITH HEAVY MUD AND SPOT CEMENT THROUGH DRILL PIPE
1ST PLUG AT 1130' WITH 50 SX CEMENT, 2ND PLUG AT 300' WITH 40 SX CEMENT,
3RD PLUG AT 40' WITH 10 SX CEMENT,
CIRCULATE RAT HOLE WITH 15 SX OF CEMENT. CIRCULATE MOUSEHOLE WITH 10 SX OF CEMENT
PUMP 100 SX OF CEMENT DOWN 10 3/4" X 8 5/8" ANNULUS

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE X

OPERATIONS COMPLETED: HOUR: 6:30PM DAY: 18 MONTH: JUNE YEAR: 1998

ACTUAL PLUGGING REPORT 1ST PLUG AT 1130' WITH 50 SX CEMENT,
2ND PLUG AT 300' WITH 40 SX CEMENT,
3RD PLUG AT 40' WITH 10 SX CEMENT,
CIRCULATE RATHOLE WITH 15 SX OF CEMENT
CIRCULATE MOUSEHOLE WITH 10 SX OF CEMENT

RECEIVED
STATE CORPORATION COMMISSION
JUN 29 1998
CONSERVATION DIVISION
Wichita, Kansas

PUMPED 80 SX OF CEMENT DOWN THE 10 3/4" X 8 5/8" ANNULUS AND IT PRESSURED UP

REMARKS: USED 60/40 POZMIX 6% GEL CEMENT PUMPED BY ALLIED CEMENTING
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID NOT) OBSERVE THIS PLUGGING.

INVOICED
DATE JUL 07 1998
INV. NO. 50864

SIGNED Richard W. Lacey
(TECHNICIAN) FORM CP-2/3