

1 040185

11-9

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,542-00-00

SW SW NE, SEC. 26, T 32 S, R 12 W ~~EX~~

2970 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4581

Lease Name Kincaid Well # 1-26

Operator: ~~EXOK~~ EXOK, Inc.

County Barber 155.03

Name & Address 6410 B. North Santa Fe

Well Total Depth 4770 feet

Oklahoma City, OK 73116

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 475

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 3:30 p.m. Day: 9 Month: 11 Year: 19 88

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4078' PRTD 4038' Perfs at 3802-94, 3751-54'

1st plug sand back to 3700' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 15 1988

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 9 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3700' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 600 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 2% gel, 2% cc, by B.J. Titan. Recovered 2950' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE 11-21-88

Signed Stephen J. Pfeiffer
(TECHNICIAN)

INV. NO. 23037