

To: 1040695
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 150' W SE NW, SEC. 27, T. 32 S, R. 12
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-1 API NUMBER 15- 007-22,360 - 00-01 390

TECHNICIAN'S PLUGGING REPORT

Operator License # 30211

Operator: Coats & Malone, Inc.
Name & Address: 1007 E. 2nd
Wichita, KS 67214

3300 feet from S section line
3450 feet from E section line

Lease Name Ash Well # 1
County Barber 160.06

Well Total Depth 4925 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 515

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:30 a.m. Day: 1 Month: 9 Year: 19 92

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4924' w/150 sx cement, PBSD 4775', Perfs at 4812-18, 4823-27, 4450-70'

1st plug sand back to 4775'-4400' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 5 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 1 Month: 9 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 5 sx gel,

100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 650 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3850' of 4 1/2" casing.

INVOICED

observe this plugging.

DATE 10-2-92

INV. NO. 36305

Signed [Signature] (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION 9-15-92 SEP 15 1992 CONSERVATION DIVISION Wichita, Kansas