

1 010245

MAY 2 1 1987

API NUMBER 15-007-20,287-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SW NE, SEC. 28, T 32 S, R 12 W/E
2970 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Lease Name Ash Well # 1

Operator: Edmiston Oil Company, Inc.
Name & Address 1260 Kansas State Bank Bldg.
Wichita, KS 67202

County Barber 146.54
Well Total Depth 4509' feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 285

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:45 p.m. Day: 21 Month: 5 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4509' Perfs at 4447-57' Elevation 1627'KB

1st plug pump 2 sx hulls and 25 sx cement to bottom,

2nd plug pump 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15 p.m. Day: 21 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 3 sx hulls and 25 sx common cement,

2nd plug pumped 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement. (Used 60/40 Pozmix 6% gel for this plug.)

Maximum pressure 800 psi and shut in 500 psi.

Remarks: Used common cement and 60/40 Pozmix 6% gel by Allied. Recovered 3550' casing.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED
DATE 5-27-87
INV. NO. 16985

Signed Paul Luthi
(TECHNICIAN)
MAY 26 1987
STATE CORPORATION COMMISSION
Conservation Division
Wichita, Kansas