

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23846-00-00
Spot: SEWNWE Sec/Twnshp/Rge: 28-10S-24W
990 feet from N Section Line, 1650 feet from E Section Line
Lease Name: HEIER Well #: 1-28
County: GRAHAM Total Vertical Depth: 4066 feet

Operator License No.: 31160
Op Name: PHILLIPS EXPLORATION COMPANY INC
Address: PO BOX 850
ANDOVER, KS 67002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3970		
DVT	5.5	2049		370 SX
PROD	5.5	4065		165 SX
SURF	8.625	210		150 SX

Handwritten signature

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/11/2013 12:00 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER WELL SERVICE, INC.
Proposal Rcvd. from: JAMES B. PHILLIPS Company: FISCHER WELL SERVICE, INC. Phone: (316) 636-2256

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls and 14 sx gel. Perforations at 3966' - 3970'. DV Tool at 2049' w/370 sx cement.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/11/2013 7:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3970' and pumped 14 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 2075' and pumped 100 sx cement. Pulled tubing to 1100' and pumped 100 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing w/10 sx cement. Hole standing full. Tied on to backside and squeezed w/5 sx cement. Shut in pressure 150 psi.
GPS: 39.15820 -100.00211

Perfs:

Top	Bot	Thru	Comments
3966	3970		
3941	3946		

Remarks: QUALITY OILWELL CEMENT TICKET # 7532

Plugged through: TBG

District: 04

Signed

Handwritten signature
10/15/13

(TECHNICIAN) RECEIVED
KANSAS CORPORATION COMMISSION

CM

OCT 15 2013

OCT 21 2013

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS