

6-13

2-100710 166
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

TMB
KCC

API NUMBER: ⁰⁷⁷ 15-~~007~~-20,864-⁰⁰⁰⁰ D-22,005

E/2 SE NE, SECTION 30 TOWNSHIP 32 RANGE 9W

OPERATOR LICENSE # 5428 2970 FEET FROM S SECTION LINE
660 FEET FROM E SECTION LINE

OPERATOR Graves Drilling
NAME & 8100 East 21st, Box 8250
ADDRESS Wichita, KS 67208-0250

LEASE NAME: Joseph #1

COUNTY: Harper 141.37

WELL TOTAL DEPTH: 4350' PB 3674'

PIPE: 4-1/2" @ 3731'/150 sx

SURFACE CASING: 8-5/8" @ 238'/200 sx

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SMD D&A _____

OTHER WELL AS HEREINAFTER INDICATED: Perf 3510'-3590'

PLUGGING CONTRACTOR: Clark Corporation
ADDRESS: Box 187, Medicine Lodge, KS 67104 LICENSE: 5105

COMPANY TO PLUG AT: HOUR: 9:00a DAY: 13 MONTH: 6 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Elmo Morgensten
COMPANY NAME: Clark Corporation PHONE: _____

WERE: Sand 3764' - 3470' - 4 sx cmt - 35 sx @ 1450' - 35 sx @ 850' - circ @ 300'

PLUGGING PROPOSAL RECEIVED BY: Steve VanGieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (_____) NONE (_____)

COMPLETED: HOUR: 12:00p DAY: 13 MONTH: 6 YEAR: 1991

ACTUAL PLUGGING REPORT:
Sanded back to 3470' & dumped 4 sx w/bailer - shot 2800' of 4-1/2" and pulled to 1422' - spotted 35 sx of cmt - pulled to 857' & spotted 35 sx cmt - pulled to 304' & circ to surface.

REMARKS: ~~REB~~ J. Titan #636523 60/40 4%

STATE CORPORATION COMMISSION
I DID OBSERVE THIS PLUGGING.

J. L. Sanders
J. L. Sanders (AGENT)

INVOICE # 6-24-91

DATE JUL 19 1991

INV. NO. 32318