

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21402-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 34-32S-9W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: MCDANIEL TRUST A Well Number: 1-34
County: HARPER Total Vertical Depth: 3849 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 453 S. WEBB RD. STE 310 PO BOX 7802
WICHITA, KS 67278

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 262
Production: Size feet:
Liner: Size feet:

\$125.09

Well Type: GAS UIC Docket No: Date/Time to Plug: 05/24/2001 1:15 AM
Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.
Proposal Rcvd. from: MIKE PICKRELL Company: PICKRELL DRILLING COMPANY, I Phone: (316) 262-8427

Proposed Plugging Method: Fill hole with heavy mud and spot cement through drill pipe. Spot 35 sxs. cement at 875', spot 35 sxs. cement at 310', spot 25 sxs. cement at 60', and fill rathole with 10 sxs. cement.

Plugging Proposal Received By: MICHAEL WILSON
Date/Time Plugging Completed: 05/24/2001 2:30 AM

Witness Type: Plugging Operations Were Not Witnessed
KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Filled hole with heavy mud and spotted cement through the drill pipe. Spotted 35 sxs. cement at 875'. Spotted 35 sxs. cement at 310'. Spotted 25 sxs. cement at 60'. Filled rathole with 10 sxs. cement.

INVOICED
DATE 6-14-01
WV. NO. 2001061940

RECEIVED
KCC DISTRICT #2
JUN 14 2001
6-14-01
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY ACID SERVICES. INVOICE # 3253

Plugged through: DP

District: 02

Signed Michael Wilson
(TECHNICIAN)