

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-22052-00-00  
Spot: NENESE Sec/Twnshp/Rge: 13-19S-22W  
2310 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: SCHWIEN Well Number: 1  
County: NESS Total Vertical Depth: 4315 feet

Operator License No.: 3759  
Op Name: SCHWIEN TANK & LEASE SERVICE INC  
Address: PO BOX 86  
BAZINE, KS 67516

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 450 WITH 225 SX CMT <sup>\$</sup> 14024  
Production: Size 4.5 feet: 1422 WITH 425 SX CMT  
Liner: Size feet:

Well Type: SWD UIC Docket No: D22484.0 Date/Time to Plug: 04/26/2001 4:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: TED FUCHS Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: PUMP WATER TO SEE IF PERFORATIONS WERE OPEN. PUMPED 3 BBL A MINUTE AT 450#. MIXED 70 SX CMT WITH 100# HULLS AT FIRST AND THEN SHUT OFF. MAXIMUM PRESSURE 500#. TIED ONTO BACKSIDE AND PUMPED 10 SX CMT AND SHUT OFF WITH 500#. HELD.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 04/26/2001 4:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 1380'. PERFS AT 950-1100'. PUMP WATER TO SEE IF PERFORATIONS WERE OPEN. PUMPED 3 BBL A MINUTE AT 450#. MIXED 70 SX CMT WITH 100# HULLS AT FIRST AND THEN SHUT OFF. MAXIMUM PRESSURE 500#. TIED ONTO BACKSIDE AND PUMPED 10 SX CMT AND SHUT OFF WITH 500#. HELD.

INVOICED  
DATE 5-14-01  
NO. 2001061799

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 14 2001  
5-14-01  
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Michael Maier  
(TECHNICIAN)

MAY 02 2001

Form CP-43