

To: 1 070894  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-20,647-00-00

C SW SE, SEC. 13, T 19 S, R 22 W/E

660 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4058

Lease Name Schwein Well # 1

Operator: American Warrior, Inc.

County Ness 141.24

Name & Address Box 399

Well Total Depth 4346 feet

Garden City, KS 67846

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 323

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:45 a.m. Day: 13 Month: 12 Year: 19 90

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 4333' w/100 sx cement, Open hole at 4333-46'

1st plug sand back to 4280' and dump 5 sx cement on top of sand through bailer,

2nd plug at 1480' with 50 sx cement,

3rd plug at 700' with 80 sx cement,

4th plug at 370' with 50 sx cement, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:45 p.m. Day: 13 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4280' and dumped 5 sx cement on top of sand through bailer,

2nd plug pulled casing up to 1480' and pumped 50 sx cement,

3rd plug pulled to 700' with 80 sx cement,

4th plug pulled to 370' with 50 sx cement,

5th plug topped off with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 5 1/2" casing.

additional description is necessary, use BACK of this form.)

(old / ~~XXXXXX~~) observe this plugging.

DATE 1-8-91

Signed Dan Johnson  
(TECHNICIAN)

INV. NO. 30392

12-12 MAR 07 1991 FEB 27 1992

INVOICED

RECEIVED  
STATE CORPORATION COMMISSION  
12-19-90  
DEC 19 1990  
CONSERVATION DIVISION  
Wichita Kansas