

1050589

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION N/2 N/2 NE, SEC. 10, T 19 S, R 22
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,882 -0660

4950 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9883

Lease Name Shriock Well # 2

Operator: Sharon Resources, Inc.

County Ness 142.35

Name & Address 7100 East Belleview Avenue

(Mississippi) Well Total Depth 4380 feet

Englewood, CO 80211

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 379

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Co. License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 2:00 am Day: 2 Month: August Year: 1985

Plugging proposal received from Steve Merica

(company name) Red Tiger (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1456-88

1st plug at 1470' with 50 sx cement

2nd plug at 900' with 70 sx cement

3rd plug at 390' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30 am Day: 2 Month: August Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 1470' with 50 sx cement, 2nd plug at 900' with

70 sx cement, 3rd plug at 390' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton

(if additional description is necessary, use BACK of this form.)

INVOICED

AUG 07 1985

DATE

9416

INV. NO.

SEP 11 1985

OCT 11 1985 CONSERVATION DIVISION

RECEIVED

8-5-85
AUG 5 1985

Signed Richard W. Lacey (TECHNICIAN)