

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20242-00-00
Spot: SENWSW Sec/Twnshp/Rge: 19-13S-21W
1650 feet from S Section Line, 4290 feet from E Section Line
Lease Name: PETTY C Well #: 1
County: TREGO Total Vertical Depth: 4082 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 S MAIN STE 505
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3850		
PROD	5.5	4077		225 SX
SURF	8.625	257		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/08/2013 10:00 AM

Plug Co. License No.: 5121 Plug Co. Name: MOBILE DRILLING COMPANY, INC.

Proposal Rcvd. from: ED MONDERO Company: MOBILE DRILLING COMPANY, IN Phone: (620) 793-2315

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Perforations at 3817' - 3820', 3672' - 3677', 3636' - 3641'.
Squeezed at 958' to 1232' w/200 sx cement. Squeezed at 1360' with 100 sx cement.
Shot perforations at 250', 885', 1710' and 2250'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/08/2013 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3833' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 2844' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 1888' and pumped 190 sx cement. Good circulation of cement. Pulled tubing out. Tied on to casing and squeezed w/60 sx cement. Casing and backside are full of cement.

GPS: 39.90455 -099.70280

Perfs:

Top	Bot	Thru	Comments
3817	3820		
3672	3677		
3636	3641		

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: SWIFT CEMENTI TICKET # 25132

OCT 15 2013

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed  (TECHNICIAN) CM

OCT 09 2013