

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26576-00-00
Spot: NENWSENE Sec/Twnshp/Rge: 2-15S-18W
1495 feet from N Section Line, 975 feet from E Section Line
Lease Name: DONALD Well #: 1
County: ELLIS Total Vertical Depth: 3655 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
STRL	8.625	215		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/05/2013 12:00 AM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: DOUG Company: ROYAL DRILLING INC Phone: (785) 735-4142-

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: NONE
Date/Time Plugging Completed: 08/05/2013 10:15 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

1st plug @3635 w/50 sx
2nd plug @1215 w/25 sx
3rd plug @500 w/80 sx
4th plug @275 w/40 sx
5th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs: _____

Remarks: QUALITY

Plugged through: DP

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 11 2013

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Darrel Dipman
08/24/13 (TECHNICIAN)

CM

AUG 26 2013

Form CP-2/3