

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-26592-00-00  
Spot: W2SWSESE Sec/Twnshp/Rge: 14-11S-18W  
330 feet from S Section Line, 1270 feet from E Section Line  
Lease Name: LYNN Well #: 1-14  
County: ELLIS Total Vertical Depth: 3500 feet

Operator License No.: 30129  
Op Name: EAGLE CREEK CORPORATION  
Address: 150 N MAIN STE 905  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	263		190 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/11/2013 12:00 AM  
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.  
Proposal Rcvd. from: JAY Company: SOUTHWIND DRILLING, INC. Phone: (620) 617-4477

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/11/2013 10:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

1st plug @3467 w/50 sx  
2nd plug @1210 w/25 sx  
3rd plug @605 w/100 sx  
4th plug @315 w/40 sx  
5th plug @40 w/10 sx

Rathole 30 sx

Remarks: QUALITY

Plugged through: DP

KCC WICHITA  
SEP 17 2013  
RECEIVED

District: 04

Signed [Signature]  
09/24/13 (TECHNICIAN)

CM

SEP 12 2013

Form CP-2/3