

To: 1 051152
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-10
API NUMBER 15- 165-21,466 -0000

NW NE SW, SEC. 22, T 19 S, R 16 WXB
2310 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7261 & 5122

Lease Name Dyer Well # 1

County Rush 124.64

Well Total Depth 3835 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 238

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Woodman-Iannitti Drilling License Number 5122

Address P.O. Box 308, Great Bend, KS 67530

Company to plug at: Hour: 6:15 p.m. Day: 10 Month: 4 Year: 19 89

Plugging proposal received from Rich Wheeler

(company name) Woodman-Iannitti Drilling (phone) 316-792-1922

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1069-98'

1st plug at Arbuckle with 50 sx cement, 2nd plug at 1090' with 50 sx cement

3rd plug at 500' with 60 sx cement, 4th plug at 260' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 13 1989

4-13-89
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:20 p.m. Day: 10 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 3709' with 50 sx cement,

2nd plug at 1090' with 50 sx cement,

3rd plug at 500' with 60 sx cement,

4th plug at 260' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INNOVATED (did not) observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

DATE 4-24-89

INV. NO. 24452

4-10 JUN 12 1989

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date March 25 1989 NW. NE. SW. Sec. 22 Twp. 19 S, Rg. 16 X East
month day year

OPERATOR: License # 7261 & 5122
Name: Pate-Dombaugh, INC. & Woodman-Iannitti Drlg.
Address: 804 Union Center Bldg.
City/State/Zip: Wichita, KS. 67202
Contact Person: Don R. Pate
Phone: 316-262-5993

..... 2310 feet from South line of Section
..... 3630 feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 5122
Name: WOODMAN-IANNITTI

County: Rush
Lease Name: Dyer Well #: 1
Field Name: Wildcat
Is this a Prorated Field? yes X no
Target Formation(s): Arbuckle
Nearest lease or unit boundary: 330 Ft.
Ground Surface Elevation: 2015 Est. feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 180 Ft.
Depth to bottom of usable water: 350 Ft.
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 200 Ft.
Length of Conductor pipe required: 0
Projected Total Depth: 3800 Ft.
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:
..... well farm pond X other

Well Drilled For: Well Class: Type Equipment:
X Oil ... Inj ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OAWO ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes

If OAWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

DWR Permit #:
Will Cores Be Taken? yes X no
If yes, proposed zone:

Spud 4-3-89

Spt 200'
AFFIDAVIT

200' Act. 2 Reg.

PUSHER Rich Wheeler
TD 38 35 FORMATION Arb.
SURFACE PIPE 8 3/4 @ 2 3/8
ANHYDRITE 100 9-98 ELEVATION
STARTING TIME & DATE 6:15 PM 4-10-89
COMPLETION TIME & DATE 9:20 PM
1st PLUG @ Arb FT. W/ 50 SX
2nd PLUG @ 1090 FT. W/ 50 SX
3rd PLUG @ 500 FT. W/ 60 SX
4th PLUG @ 260 FT. W/ 40 SX
RAI HOLE CIRCULATED W/ 15 SX
MOUSE-HOLE CIRCULATED W/ _____ SX
WATER-WELL-PLUGGED W/ _____ SX

CEMENT COMPANY Allied
TECHNICIAN R. L. O.G.

60/400%

RECEIVED
STATE CORPORATION COMMISSION
APR 13 1989
4-13-89
CONSERVATION DIVISION
Wichita, Kansas

5280	1650
4950	1320
4620	990
4290	660
3960	330
3630	
3300	
2970	
2640	
2310	
1980	
1650	
1320	
990	
660	
330	

Wichita, Kansas

REMEMBER TO:

- File Drill Pit Application (form CDP-1) with Intent to Drill;
- File Completion Form ACO-1 within 120 days of spud date;
- File acreage attribution plat according to field proration orders;
- Notify appropriate district office 48 hours prior to workover or re-entry;
- Submit plugging report (CP-4) after plugging is completed;
- Obtain written approval before disposing or injecting salt water.