

4-13 416

To: 1 020372
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,359-00-00
NE SW NW, SEC. 28, T. 33 S, R. 12 W/E
3695 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3122
Operator: Vintage Petroleum, Inc.
Name & Address: 4200 One Williams Center
Tulsa, OK 74172

Lease Name R.M. Watts Well # 28-1
County Barber 165.75
Well Total Depth 5100 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Val Energy Inc. License Number 5822
Address P.O. Box 322, Haysville, KS 67060

Company to plug at: Hour: 5:30 a.m. Day: 13 Month: 4 Year: 19 91

Plugging proposal received from Todd Allam
(company name) Val Energy Inc. (phone) 316-583-8681

were: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 5100' with 50 sx cement, 2nd plug at 550' with 50 sx cement,
3rd plug at 300' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn R. Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:30 p.m. Day: 13 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 5050' with 50 sx cement,
2nd plug at 550' with 50 sx cement,
3rd plug at 308' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services.
(If additional description is necessary, use BACK of this form.)

INVOICED (XXXX) observe this plugging.

Signed Glenn R. Barlow (TECHNICIAN)

DATE 5-13-91
INV. NO. 31809

4-13 AUG 12 1991