

1 040341

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-22,264 - 00-00

C SW NE, SEC. 19, T 33 S, R 15 W/E

3300 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3080

Lease Name Brass Well # 1-19

Operator: Jack Exploration, Inc.

County Barber 174.69

Name & Address P.O. Box 60

Well Total Depth 5375 feet

Sulphur, OK 73086

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 352

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Eagle Drilling, Inc. License Number 5380

Address 2759 South Broadway, Wichita, KS 67216

Company to plug at: Hour: 5 p.m. Day: 29 Month: 10 Year: 1989

Plugging proposal received from Butch Steinert

(company name) Eagle Drilling, Inc. (phone) 316-945-9935

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 725-35'

1st plug at 740' with 50 sx cement, 2nd plug at 380' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7 p.m. Day: 29 Month: 10 Year: 1989

ACTUAL PLUGGING REPORT 1st plug at 740' with 50 sx cement,

2nd plug at 380' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

11-1-89

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-2-89

INV. NO. 26305

10-29

Signed Stephen J. Pfeifer (TECHNICIAN)