

7-13

040293

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,129-00-00
C. NW NW, SEC. 21, T 33 S, R 15 W/E
4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6769
Operator: Westmore Drilling
Name & Address: P.O. Box 34
Medicine Lodge, KS 67104

Lease Name Mitchell Well # 1
County Barber 179.21
Well Total Depth 5514 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 255

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11:15 a.m. Day: 13 Month: 7 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 5468' PBT 4660' Perfs at 4627-4631'
1st plug sand back to 4660-4575' with 5 sx cement on top of sand with bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 13 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back from 4660-4575' and put 4 sx cement on top of sand bridge with bailer,
2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Maximum pressure 200 psi and shut in 100 psi.

RECEIVED STATE CORPORATION COMMISSION

7-19-89 IIII 19 1989

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2700' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (If you observe this plugging.)

DATE 7-21-89
INV. NO. 25392

Signed Stephen J. Taylor (TECHNICIAN)