

1052335

TO: STATE CORPORATION COMMISSION API NUMBER 15-007-22,599-00-00
250' N OF NW NW SEC. 31, T 33 S, R 15 W

8-29-99

CONSERVATION DIVISION - PLUGGING SECTION 410 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME REED WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY BARBER

OPERATOR LICENSE # 5050 WELL TOTAL DEPTH 5470 FEET

OPERATOR: HUMMON CORPORATION PRODUCTION CSG: SIZE " FEET

NAME AND 950 N TYLER SURFACE CASING: SIZE 8 5/8" @ 909' WITH SX

ADDRESS WICHITA, KS 67212-3240 SURFACE CASING: SIZE 10 1/4" @ 268' WITH SX

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DUKE DRILLING LICENSE NUMBER 5929

ADDRESS 100 S MAIN, SUITE 410, WICHITA, KS 67202-3737

COMPANY TO PLUG AT: HOUR: 9:00 PM DAY: 28 MONTH: 08 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM JOE

(COMPANY NAME) DUKE DRILLING (PHONE) 316-267-1331

WERE:

1ST PLUG PUMP 100 SX CEMENT DOWN 8 5/8" X 10 1/4" ANNULUS. 2ND PLUG AT 900' WITH 50 SX CEMENT.

3RD PLUG AT 310' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

INVOICED

DATE 9-22-99

INV. NO. 10090

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 1:00 AM DAY: 29 MONTH: 08 YEAR: 1999

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG PUMP 100 SX CEMENT DOWN 8 5/8" X 10 1/4" ANNULUS. 2ND PLUG AT 900' WITH 50 SX CEMENT.

3RD PLUG AT 310' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

RECEIVED STATE CORPORATION COMMISSION

9-20-99 SEP 20 1999

CONSERVATION DIVISION Wichita, Kansas

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

SIGNED Richard M. Lacey (TECHNICIAN)

FORM CP-2/3

Handwritten initials and signature in a circle.