

To: 1 051065
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3399

Operator: Farrar Pump & Supply Co., Inc.
Name & Address: P.O. Box 209
Medicine Lodge, KS 67104

6-28-88 15-007-00313-00-00 330
API NUMBER 15- Drill Completion Date 3/27/62

SE SW NE, SEC. 13, T 33 S, R 12 W 1/4
2970 feet from S section line
1650 feet from E section line

Lease Name Harbaugh Well # B 1

County Barber 156.98

Well Total Depth 4830 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 225

Abandoned Oil Well Gas Well ☒ Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 107, Medicine Lodge, KS 67104

Company to plug at: Hour: 1 p.m. Day: 28 Month: 6 Year: 19 88

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4467' PBTD 4467'

1st plug sand back to 4350' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part None

Operations Completed: Hour: 2:20 p.m. Day: 28 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

Maximum pressure 700 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3422' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.) Kansas

INVOICED

DATE 7-19-88

INV. NO. 21428

Signed Richard M. Lutz
(TECHNICIAN)