

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW/4, Sec. 13, T 33 S, R 12 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007- 21,697 -00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

feet from N/S section line
feet from W/E section line

Operator: Hummon Corporation
Name & Address: 400 One Main Place, Suite 400
Wichita, KS67202

Lease Name Groendyke Well # 1
County Barber

Well Total Depth 3830 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 223

Abandoned Oil Well X Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5154
Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:00 am Day: 7 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Elmo Morgenstern
(company name) Clarke (phone) 316-886-5665

were: PBSD 3708 Top Perfs at 3626 to 34. 5 1/2 set at 3737

1st plug sand back to 3575 and dump 5 sx cement on top of sand through bailer.

2nd plug 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and released

8 5/8" rubber plug and pumped an additional 100 sx cement.

Maximum pressure 500# and shut-in pressure 300#

Signed (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:30 am Day: 7 Month: February Year: 19 84

ACTUAL PLUGGING REPORT PBSD 3708 Top Perfs at 3626 to 34 5 1/2 set at 3737

1st plug sand back to 3575 and dump 5 sx cement on top of sand through bailer.

2nd plug 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and released

8 5/8" rubber plug and pumped an additional 100 sx cement.

Maximum pressure 500# and shut-in pressure 300#.

Remarks: They recovered 3000' of 5 1/2. Use 60/40 Pozmix 2% gel 3% cc. by Sun
Blew 2" nipple at 500# pressure.

I hereby certify that the above plugging instructions were given as here stated
and that I (did / ~~did not~~) observe this plugging.

RECEIVED STATE CORPORATION COMMISSION
FEB 15 1984
CONSERVATION DIVISION
Wichita, Kansas

Signed (TECHNICIAN)

INVOICED

DATE 2-22-84

INV. NO. 0292