

To: 1 051067
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION N/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-1-88
API NUMBER 15-165-21,425-0000
SE NE, SEC. 31, T 19 S, R 19 W/R
3630 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3532
Operator: CMX, Inc.
Name & Address 1026 Union Center Building
Wichita, KS 67202

Lease Name Maresch Well # 2-31
County Rush 141.38
Well Total Depth 4350 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Rains & Williamson License Number 5146

Address 435 Page Court, 220 West Douglas, Wichita, KS 67202

Company to plug at: Hour: 4 p.m. Day: 1 Month: 7 Year: 19 88

Plugging proposal received from Louis Burgess

(company name) Rains & Williamson (phone) 316-265-9686

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2273' Anhydrite 1451'

1st plug at 1470' with 50 sx cement, 2nd plug at 780' with 80 sx cement,
3rd plug at 240' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 6 p.m. Day: 1 Month: 7 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1470' with 50 sx cement,

2nd plug at 780' with 80 sx cement,
3rd plug at 240' with 40 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1988
7-12-88
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Richard W. Lutz (TECHNICIAN)

INVOICED
DATE 7-21-88

INV. NO. 21507 SEP 12 1988

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date: June 20, 1988
month day year

API Number 15-165-21,425-0000

OPERATOR: License # 03532
Name CMX, Inc.
Address 1026 Union Center Building
City/State/Zip Wichita, Kansas 67202
Contact Person Doug McGinness II
Phone (316) 269-9052

N/2 SE NE Sec. 31 Twp. 19 S, Rg. 19
3630 Ft. from South Line of Section
660 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5146
Name Rains & Williamson
City State Wichita, Kansas

Nearest lease or unit boundary line
County Rush

Well Drilled For: Well Class: Type Equipment:
 Oil Storage Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Lease Name Maresch Well # 2-31
Ground surface elevation Not Available feet MSL

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 06-10-88 Signature of Operator or Agent Title President

Depth to bottom of fresh water 100'
Depth to bottom of usable water 500'

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. 2
This Authorization Expires 12-14-88 Approved By Jeth 6-14-88

Surface pipe by Alternate 1-2
Surface pipe planned to be set 200'

Conductor pipe required None
Projected Total Depth 4350 feet

EFFECTIVE DATE: 6-19-88

Spud 6-24-88

200' + 8 5/8"

NO W.W.

N/2 SE NE Sec. 31 Twp. 19 S, Rg. 19 East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

| | | | | | |
|---------------------|-------------------|-------------------|----|---------|-----------|
| 1st plug @ ft. deep | Base Anhydrite | or formation with | 40 | feet of | 60-40 Poz |
| 2nd plug @ ft. deep | 1/2 Anhydrite | or formation with | 80 | feet of | 60-40 Poz |
| 3rd plug @ ft. deep | 30' Below Surface | or formation with | 30 | feet of | 60-40 Poz |
| 4th plug @ ft. deep | 40' | or formation with | 10 | feet of | 60-40 Poz |
| 5th plug @ ft. deep | | or formation with | | feet of | |

(2) Rathole to surface minus 5 feet

RECEIVED
Conservation Commission

Nekom 75-

PUSHER Louis Burgess
TD 4350 FORMATION Kinerhook
SURFACE PIPE 8 5/8 @ 215
ANHYDRITE 1451 ELEVATION 2273
STARTING TIME & DATE 4 pm 7-1
COMPLETION TIME & DATE 6 pm
1st PLUG @ 1470 FT. W/ 50 SX
2nd PLUG @ 1800 FT. W/ 80 SX
3rd PLUG @ 240 FT. W/ 40 SX
4th PLUG @ 40-0 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ Hand SX
CEMENT COMPANY 6/4 Poz 690 gal
TECHNICIAN J.D. BUTER
Lacey saw part
Log - now
2 hrs.
3:00 pm -
G.B 316-753-10
Burdett

JUL 12 1988
7-12-88
CONSERVATION DIVISION
Wichita, Kansas