

4-12-88

34F
L

1 051035

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,410 -0000
150' N of
E/2 NE SW, SEC. 31, T 19 S, R 19 W/E
2130 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3532

Lease Name Price Well # 1-31

Operator: CMX, Inc.

County Rush 140.73

Name & Address 1026 Union Center Building

Well Total Depth 4330 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 224

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 6 a.m. Day: 12 Month: 4 Year: 19 88

Plugging proposal received from Pat Waggoner

(company name) Red Tiger Drilling Company (phone) 316-263-1201

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1431-59' Elevation 2254' GL

1st plug at 1460' with 50 sx cement, 2nd plug at 750' with 80 sx cement,

3rd plug at 250' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8 a.m. Day: 12 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1460' with 50 sx cement,

2nd plug at 750' with 80 sx cement,

3rd plug at 250' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-20-88

APR 14 1988
4-14-88

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 20378

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date: April 1, 1988 month day year

API Number 15-165-21410-0000 150' North of E/2 NE SW Sec. 31, Twp. 19 S, Rg. 19 East 2130 Ft. from South Line of Section 2970 Ft. from East Line of Section

OPERATOR: License # 03532 Name CMX, Inc. Address 1026 Union Center Building City/State/Zip Wichita, Kansas 67202 Contact Person Doug McGinness, II Phone (316) 269-9052

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 510 feet County Rush

CONTRACTOR: License # 5302 Name Red Tiger City/State Wichita, Kansas

Lease Name Price Well # 1-31 Ground surface elevation feet MSL Domestic well within 330 feet: yes X no

Well Drilled For: X Oil Storage Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl X Wildcat Cable

Municipal well within one mile: yes X no Depth to bottom of fresh water 100' Depth to bottom of usable water 500' Surface pipe by Alternate: 1 2 X

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Surface pipe planned to be set 200 Conductor pipe required None Projected Total Depth 4300 feet Formation Basal Pennsylvanian

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plug the hole to KCC specifications. Date 03-23-88 Signature of Operator or Agent Title President

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X(2) This Authorization Expires 7-25-88 Approved By 3-25-88

EFFECTIVE DATE: 3-30-88

Spud 4/1/88 5:00 PM 200' 8 1/8

150' North of E/2 NE SW Sec. 31, Twp. 19 S, Rg. 19 East X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug depth, Formation, and Feet of 60-40 Poz. Mix. Includes entries for 1st through 5th plugs and Rathole to surface minus 5 feet.

Vertical list of plugging details: PUSHER Pat Wagner, TD 4330 FORMATION Penns., SURFACE PIPE 8 5/8 @ 224, ANHYDRITE 149/149 ELEVATION 22546L, STARTING TIME & DATE 6:00 am 4-12-88, COMPLETION TIME & DATE 8:00 am 4-12-88, 1st PLUG @ 1460 FT. W/ 50 SX, 2nd PLUG @ 750 FT. W/ 80 SX, 3rd PLUG @ 250 FT. W/ 40 SX, 4th PLUG @ 40 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY BT Titan

TECHNICIAN Lacey, RECEIVED APR 14 1988 4-14-88 CONSERVATION DIVISION Wichita, Kansas