

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20303-00-00
Spot: SESESE Sec/Twnshp/Rge: 15-10S-19W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: NUTSCHA Well #: 1
County: ROOKS Total Vertical Depth: 3729 feet

Operator License No.: 3444
Op Name: KARLIN, GENE DBA GENE KARLIN CO
Address: 1111 OAKMONT ST
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3678		
PROD	5.5	3720		150 SX
SURF	8.625	251		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/14/2013 8:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: GENE KARLIN Company: GENE KARLIN CO. Phone: (785) 483-2025

Proposed
Plugging
Method:

Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.
No Alt II records. Production perforations: 3375' - 3584'. CIBP at 3678'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/14/2013 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 2 holes at 2050', 1510' and 950'. Ran tubing to 3500'. Quality Oilwell pumped 100 sx cement w/200 # hulls. Pulled tubing to 2600' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1600' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 700' and pumped 40 sx cement. Cement circulated. PTOH. Topped 5 1/2" casing w/15 sx cement. Casing full. Backside had instant pressure at 300 psi.

Perfs:

Top	Bot	Thru	Comments
3580	3584		
3543	3546		
3473	3476		
3451	3454		
3443	3447		
3424	3429		
3392			
3375			

Remarks: QUALITY OILWELL

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

✓ 11/22/2013

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

OCT 15 2013

OCT 23 2013

CONSERVATION DIVISION
WICHITA, KS