

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21732-00-00
Spot: SESENWSE Sec/Twnshp/Rge: 14-22S-15W
1388 feet from S Section Line, 1347 feet from E Section Line
Lease Name: BLACKWELL Well #: 1
County: PAWNEE Total Vertical Depth: 4040 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	912		WITH 450 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/10/2013 9:00 AM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: CODY ROACH Company: ROYAL DRILLING INC Phone: (785) 483-6446

Proposed Plugging Method: 1ST PLUG AT 3940' WITH 50 SX CMT. 2ND PLUG AT 940' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 10/10/2013 11:00 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

1ST PLUG AT 3940' WITH 50 SX CMT. 2ND PLUG AT 940' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 15 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: DP

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
OCT 11 2013
KCC DODGE CITY

✓ 11/21/13

[Handwritten initials]