

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25880-00-00
Spot: NWNENW Sec/Twnshp/Rge: 18-18S-13W
330 feet from N Section Line, 1650 feet from W Section Line
Lease Name: FE Well #: 1
County: BARTON Total Vertical Depth: 3480 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	810		350 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/18/2013 12:00 AM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: TOM Company: ROYAL DRILLING INC Phone: (303) 618-1037

Proposed Plugging Method: Ordered 205 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE RODIE Witness Type: NONE
Date/Time Plugging Completed: 09/18/2013 10:30 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

1st plug @3270 w/50 sx
2nd plug @860 w/40 sx
3rd plug @330 w/60 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

KCC WICHITA
NOV 07 2013
RECEIVED

District: 04

Signed Bruce Rodie
(TECHNICIAN)

✓ 11/21/13

CM

Form CP-2/3

SEP 26 2013