

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20261-00-00
Spot: NENE Sec/Twnshp/Rge: 21-21S-40W
4620 feet from S Section Line, 660 feet from E Section Line
Lease Name: PETTIT Well #: A 1-21
County: HAMILTON Total Vertical Depth: 2900 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2893	0	WITH 500 SX CMT
SURF	8.625	312		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/08/2013 10:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Revd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (405) 935-7290

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/08/2013 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 40 SX CMT & 150# HULLS FROM 2778' TO 2140'. PRESSURE TO 500#. RAN BOND LOG FROM 1500' TO 0'. TOC = 110'. RUN TBG TO 1200' & CIRCULATED THE 4 1/2" CASING FULL OF CMT WITH 80 SX CMT. TOOH W/TBG & TOP OFF WITH 5 SX CMT. PUMP 30 SX CMT DOWN THE 4 1/2" X 8 5/8" ANNULUS TO 400#.

Perfs:

Top	Bot	Thru	Comments
2771	2778		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed *Ken Jehlik*
11/21/13
(TECHNICIAN)

RECEIVED
OCT 15 2013
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3
OCT 22 2013
CONSERVATION DIVISION
WICHITA, KS

AM