

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20866-00-00
Spot: E2W2NWNW Sec/Twnshp/Rge: 34-17S-40W
660 feet from N Section Line, 335 feet from W Section Line
Lease Name: BURGARDT Well #: NO.5
County: GREELEY Total Vertical Depth: 3095 feet

Operator License No.: 33094
Op Name: CIMAREX ENERGY CO.
Address: 202 S. CHEYNNE AVE STE 1000
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3093	0	WITH 700 SX CMT
SURF	8.625	355		WITH 255 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/16/2013 10:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: MIKE FOLTZ Company: CIMAREX ENERGY Phone: (620) 287-4060

Proposed Plugging Method: PUMP 300# HULLS & 200 SX CMT. FILL TO 0'. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/16/2013 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL CASING WITH CMT FROM 2988' TO 0' USING 220 SX CMT & 300# HULLS.
PRESSURE TO 500#. HOLDING. PUMP 10 SX CMT DOWN THE ANNULUS TO 400#.
HOLDING.

Perfs:

Top	Bot	Thru	Comments
2984	2988		KRIDER
2948	2964		TOWANDA
2916	2934		UPPER FT. RILEY
2843	2847		LOWER FT. RILEY

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: CSG

District: 01

Signed

Ken Jehlik
11/21/13

(TECHNICIAN)

RECEIVED

OCT 25 2013

KCC DODGE CITY

KCC WICHITA

OCT 29 2013

RECEIVED

Form CP-2/3

ATM