

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-03200-00-00  
Spot: NESWNE Sec/Twnshp/Rge: 16-24S-18E  
865 feet from N Section Line, 864 feet from E Section Line  
Lease Name: CLINE Well #: C-18  
County: ALLEN Total Vertical Depth: 851 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.875	833		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/30/2012 12:00 AM  
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC  
Proposal Rcvd. from: REX ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: RUN 2"8RD EUE TO 869'TD. PUMP 175' CEMENT FROM TD TO 695' GEL SPACER TO 500' PUMP 50' CEMENT PLUG 500' GEL SPACER TO 300' PUMP CEMENT FROM 300' TO SURFACE TOP WELL OFF.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: NONE  
Date/Time Plugging Completed: 12/31/2012 8:00 AM KCC Agent: RYAN DULING

**Actual Plugging Report:**

Ran 2" tubing to TD. Mixed and pumped gel down the 2" at TD. Pumped 25 sacks of cement at TD. Pulled 2" up to 588'. Pumped cement through the 2" and spotted 10 sacks of cement at 588'. Pulled 2" up to 260'. Circulated cement from 260' to surface. A total of 85 sacks of cement was reported used to plug this well.

**Perfs:**

Top	Bot	Thru	Comments
833	869		OPEN HOLE

RECEIVED  
OCT 30 2013  
KCC Chanute Dist. #3  
RD

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)

✓ 11/24/13

KCC WICHITA

Form CP-2/3

NOV 01 2013

RECEIVED