

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-03216-00-00

Spot: NWNENWNE

Sec/Twnshp/Rge: 16-24S-18E

5134 feet from S Section Line, 1759 feet from E Section Line

Lease Name: CLINE

Well #: B6

County: ALLEN

Total Vertical Depth: 913 feet

Operator License No.: 5150

Op Name: COLT ENERGY INC

Address: PO BOX 388
IOLA, KS 66749

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comment</u>
PROD	4.5	871		0 SX
SURF	8	16		0 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/14/2013 12:00 AM

Plug Co. License No.: 5150

Plug Co. Name: COLT ENERGY INC

Proposal Rcvd. from: REX ASHLOCK

Company:

Phone: (620) 365-3111

Proposed Plugging Method: COMPANY UNIT RIH W/1" TO TD 871' PUMP GEL IN HOLE PUMPED 50' CMT PLUG PULL 1" TBG UP TO 500' PUMP 50' CMT PLUG PULL 1" TO 250' PUMP CEMENT TO SURFACE. PULL 1" OUT TOP WELL OFF. WE HAVE EMERGENCY APPROVAL TO PLUG THIS WELL 5-14-2013 FROM MIKE HEFFERN AT DISTRICT OFFICE #3

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: NONE

Date/Time Plugging Completed: 05/14/2013 8:00 AM

KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" down the casing 863'. Pumped cement down the 1" at TD. Pulled 1" to 300'. Circulated cement through the 1" from 300' to surface. Pull rest 1" out of the well. Topped well off with cement. A total of 60 sacks of portland cement was reported used to plug this well.

Perfs:


<u>Top</u>	<u>Bot</u>	<u>Thru</u>	<u>Comments</u>
892	910		
RECEIVED OCT 30 2013 KCC Chanute Dist. #3 RD			

Remarks:

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)
✓ 11/21/13

KCC WICHITA

Form CP-2/3

NOV 01 2013

RECEIVED