

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20334-00-00
Spot: SESE Sec/Twnshp/Rge: 10-22S-42W
660 feet from S Section Line, 4620 feet from W Section Line
Lease Name: CHEATUM A Well #: 2A-10
County: HAMILTON Total Vertical Depth: 2700 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2700	0	WITH 550 SX CMT
SURF	8.625	368		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/08/2013 3:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (405) 935-7290

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/09/2013 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 40 SX CMT WITH 150# HULLS TO 2614'. PRESSURE TO 500#. RAN BOND LOG FROM 1300' TO 0'. TOC @ 76'. RAN TBG TO 1200' & CIRCULATE CMT TO SURFACE WITH 90 SX CMT. TOOH W/TBG & TOP OFF 4 1/2" WITH 10 SX CMT. PUMP 10 SX CMT DOWN THE ANNULUS TO 400#.

Perfs:

Top	Bot	Thru	Comments
2606	2614		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed _____

Ken Jehlik
✓ 10/21/13

(TECHNICIAN)

RECEIVED

OCT 15 2013

KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

OCT 22 2013

CONSERVATION DIVISION
WICHITA, KS

AW