

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

RECEIVED

WELL PLUGGING APPLICATION FORM
(File One Copy)

APR 13 1989
4-13-89

API NUMBER 15-007-20, 981-00-00 (of this well) CONSERVATION DIVISION
Wichita, Kansas

6/89

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR OXY USA Inc. OPERATOR'S LICENSE NO. 5447

ADDRESS P. O. Box 26100, Okla. City, OK 73126-0100 PHONE # (405) 749-2471

LEASE (FARM) Fitzgerald B WELL NO. 1 WELL LOCATION SE SW COUNTY Barber

SEC. 19 TWP. 34S RGE. 11 (~~S~~W) TOTAL DEPTH 4780' PLUG BACK TD 4717'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 1021' CEMENTED WITH 500 SACKS

CASING SIZE 5-1/2" SET AT 4778 CEMENTED WITH 225 SACKS
(Top of cement 4050')

PERFORATED AT 4676-96 (Mississippi)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

Set CIBP @+ 4600'. Place 5 sx Portland cmt. on plug.

PROPOSED METHOD OF PLUGGING Pull 5-1/2" csg. Pump down 8-5/8" as follows: 400# hulls, 10 sx gel, 50 sx 60/40 POZ w/6% gel, 10 sx gel, 100# hulls, wiper plug, 100 sx 60/40 POZ w/ 6% gel. Method discussed with Steve Pfeifer of the Dodge City Office.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Will be set with Dodge City office

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Earl Rollings - Production Foreman PHONE # (316) 672-9388

ADDRESS Box 381, Pratt, Kansas

PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050 6/89

ADDRESS Box 347, Chase, Kansas PHONE # (316) 938-2457

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Raymond Hui
(Operator or Agent)

DATE: 4-11-1989

①



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH McCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE

JUL 13 1989

EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

April 13, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

OXY USA, Inc.
P. O. Box 26100
Oklahoma City, OK 73126-0100

Fitzgerald B #1
SE SW
Sec. 19-34S-11W
Barber County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht

Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760