

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-077-20,665-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR McCoy Petroleum Corporation KCC LICENSE # 5003 6-93  
(owner/company name) (operator's)

ADDRESS 110 S. Main, Suite 500, CITY Wichita,

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 265-9697

LEASE Long WELL# 2 SEC. 16 T. 31S R. 8 (~~East~~ West)

- - - SE/4 SPOT LOCATION/QQQQ COUNTY Harper

2310 FEET (in exact footage) FROM S (circle one) LINE OF SECTION (NOT Lease Line)

410 FEET (in exact footage) FROM E (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#         

CONDUCTOR CASING SIZE          SET AT          CEMENTED WITH          SACKS

SURFACE CASING SIZE 8-5/8" SET AT 269' CEMENTED WITH 250 SACKS

PRODUCTION CASING SIZE 4-1/2" SET AT 4379' CEMENTED WITH 100 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Open Hole 4379-4388'

ELEVATION 1601GL/1611' KBT.D. 4388 PBTD          ANHYDRITE DEPTH           
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP +/- 4330' & cap with 1 Bailer cement. Shoot & pull casing according to stretch. Pull casing to 1200' and spot 35 sacks of cement. Pull casing to 800' and spot 35 sacks of cement. Pull casing to 320' and circulate cement

(If additional space is needed attach separate page)  
to surface. Pull remaining casing and top off cement. 40/60 Pozmix, 6% gel.  
IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?  IS ACO-1 FILED? Yes

If not explain why?         

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl Hanson PHONE# (316) 24-7893

ADDRESS P. O. Box 781624 City/State Wichita, KS 67202

PLUGGING CONTRACTOR Shawnee Well Service KCC LICENSE # 30346 6-93  
(company name) (contractor's)

ADDRESS P. O. Box 781624 Wichita, KS 67278 PHONE # (316) 254-7893

PROPOSED DATE AND HOUR OF PLUGGING (If Known?)         

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 10-15-92 AUTHORIZED OPERATOR/AGENT: [Signature]

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 19 1992  
10-19-92  
CONSERVATION DIVISION  
Wichita, Kansas

2)

Joan Finney  
Governor

Jim Robinson  
Chairman

F. S. Jack Alexander  
Commissioner

Rachel C. Lipman  
Commissioner

Judith McConnell  
Executive Director

Brian Moline  
General Counsel



# Kansas Corporation Commission

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

October 19, 1992

McCoy Petroleum Corp  
110 S Main 500  
Wichita KS 67202

Long 2  
API 15-077-20,665-  
2310' FSL-410' FEL 0000  
Sec. 16-31-08W  
Harper County

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams  
Production Supervisor

District: #2 202 W First Suite 304  
Wichita KS 67202  
(316) 263-8809

Conservation Division  
William R. Bryson  
Director  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, Kansas 67202-1286  
Telephone (316) 263-3238