

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

FORM CP-1
Rev. 03/92

130 S. Market, Room 2078
Wichita, Kansas 67202

RECEIVED

AUG 19 2002

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

KCC WICHITA

API #: 15-007-22713-00,00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate sp or completion date

WELL OPERATOR: National Petroleum Reserves, Inc. KCC LICENSE # 9482
(owner/company name) (operator's)

ADDRESS: 250 N. Rock Rd, #130 CITY: Wichita

STATE: Kansas ZIP CODE 67206 CONTACT PHONE: 316-681-3515

LEASE: Simpson WELL#: No. 1 Section 29 Township 31s Range 12w

120' E of Se Se SPOT LOCATION/QQQQ COUNTY: Barber

660 FEET (in exact footage) FROM South LINE OF SECTION (NOT Lease Line)

540 FEET (in exact footage) FROM East LINE OF SECTION (NOT Lease Line)

Check One: Oil Well _____ Gas Well _____ D&A XX SWD/ENHR WELL _____ Docket # _____
CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS
SURFACE CASING SIZE 8-5/8" SET AT 297.49' KB CEMENTED WITH 220 SACKS
PRODUCTION CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
ELEVATION 1544 G.L. 1553 K.B. T.D. 4537 PBDT _____ Anhydrite Depth _____
(Stone Corral Formation)

CONDITION OF WELL: GOOD XX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING:
Received plugging orders from Steve Durant on 08/13/02. Plugged on 08/15/02 using
135 sx 60/40 Poz, 2% Gel, 3% CC: Heavy Mud in hole and between all plugs. Bottom plug 50 sx at 600',
2nd plug 50 sx at 300', top plug 10 sx from 40' to surface. Completed at 9:45 am on 08/15/02.
Plugged rathole with 15 sx and mousehole with 10 sx. Acid Services ticket # 5075. KCC notified.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)
If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Name: Lanny Saloga/Gary Talbott Phone#: (620) 672-9508
Address: P.O. Box 1006 City: Pratt State: Kansas
PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142
(company name) (contractor's)
Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 9:45 am on August 15, 2002.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent _____

DATE: 08/15/02 AUTHORIZED OPERATOR OR AGENT: Gary M. Talbott
(signature) Gary M. Talbott, Agent for Operator