

STATE OF KANSAS
STATE CORPORATION COMMISSION

FORM CP-1

Rev. 03/92

RECEIVED CONSERVATION DIVISION
OCT 30 2002
KCC WICHITA

130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API #: 15-007-22720-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate sp or completion date

WELL OPERATOR: National Petroleum Reserves, Inc.
(owner/company name)

KCC LICENSE # 9482
(operator's)

3/03

ADDRESS: 250 N. Rock Rd, #130 CITY: Wichita

STATE: Kansas ZIP CODE 67206 CONTACT PHONE: 316-681-3515

LEASE: Hall WELL#: No. 3 Section 31 Township 31s Range 12w

Se Se Nw Ne SPOT LOCATION/QQQQ COUNTY: Barber

1170 FEET (in exact footage) FROM North LINE OF SECTION (NOT Lease Line)

1865 FEET (in exact footage) FROM East LINE OF SECTION (NOT Lease Line)

Check One: Oil Well Gas Well D&A XX SWD/ENHR WELL Docket #
CONDUCTOR CASING SIZE None SET AT CEMENTED WITH SACKS
SURFACE CASING SIZE 8-5/8" SET AT 278' KB CEMENTED WITH 190 SACKS
PRODUCTION CASING SIZE None SET AT CEMENTED WITH SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
ELEVATION 1532 G.L. 1541 K.B. T.D. 4537 PBDT Anhydrite Depth
(Stone Corral Formation)

CONDITION OF WELL: GOOD XX POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING:
Plugged well on 10/25/02 in this manner: Heavy mud in hole and between all plugs. Used 135 sx of 60/40 Poz, 6% Gel with bottom plug of 50sx at 600', 2nd plug of 50sx at 300', top plug of 10sx at 40' cemented to surface. Rathole 15sx and mousehole 10sx. By Acid Services, ticket #5332.
Job completed at 11:45 am on 10/25/02.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)
If not explain why

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Name: Lanny Saloga/Gary Talbott Phone#: (620) 672-9508
Address: P.O. Box 1006 City: Pratt State: Kansas

PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142
(company name) (contractor's)

Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 11:45 am on October 25, 2002

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent

DATE: 10/25/02 AUTHORIZED OPERATOR OR AGENT: Gary M. Talbott
(signature) Gary M. Talbott, Agent for Operator