

1 080586

DEC 24 1986

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5435

Operator: Bowers Drilling Company, Inc.
Name & Address 125 N. Market, #1425
Wichita, KS 67202

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Bowers Drilling Company, Inc. License Number 5435

Address 125 N. Market, #1425, Wichita, KS 67202

Company to plug at: Hour: 11 a.m. Day: 24 Month: 12 Year: 19 86

Plugging proposal received from Bill Muskgrove

(company name) Bowers Drilling Company, Inc. (phone) 316-886-5520

were: 4 1/2" at 4379' PBTD 4364' Perfs at 4315-55'

1st plug sand back to 4260' and dump 4 sx cement on top of sand through bailer,

2nd plug squeeze well with 2 sx hulls, 10 sx gel, and 150 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 24 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 75' above perforations and dump 4 sx cement on top of sand through bailer,

2nd plug pump 2 sx hulls, 10 sx gel, and 150 sx cement.

STATE CORPORATION COMMISSION
12-30-86
DEC 30 1986
CONSERVATION DIVISION
Wichita, Kansas

Maximum pressure 950 psi and shut in 700 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1100' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 12-30-86

Signed J. D. Thep
(TECHNICIAN)

INV. NO. 15673
12-24