

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 1 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
800 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Bill Nelson of Walters Drilling Company has this date requested permission to plug the following described well:

Mr. Nelson guarantees payment of the plugging fee.

Operator's full Name: Ferguson Oil Company

Complete Address: 1505 Wichita Plaza, Wichita, Kansas

Lease Name: Lee "A" Well No. # 1

Location: C NW SW Sec. 4 Twp. 30 Rge. 15 (E) (W)

County Barber Total Depth 4915 Oil Well

Gas Well    Input Well    SWD Well    D & A X Lost Hole   

Mr. Nelson was instructed to plug the well as follows:

247' of 8 5/8" surface pipe, cement circulated with 180 sacks.  
Fill hole with drilling mud to 240', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling mud  
to 40', 2nd cementing plug, bridge with hulls, and cement with 10  
to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

*Archie Elving*