

State of Kansas



JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL, Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

SEP 15 1964

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. T. R. Sullivan of Sierra Petroleum Company has this date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company Inc.

Complete Address: 1625 Wichita Plaza, Wichita, Kansas

Lease Name: Gress Well No. # 1

Location: C NE SE Sec. 3 Twp. 32 Rge. 12(E) (W) W

County Barber Total Depth 4370 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sullivan was instructed to plug the well as follows:

208' of 8 5/8" surface pipe, cement circulated. Fill hole with drilling mud to 205', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving