

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

APR 8 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Buck Smith of Glen and Smith has this

date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Stelbar Oil Corporation Inc.

Complete Address: 310 Petroleum Bldg., Wichita, Kansas

Lease Name: Hoyt Well No. # 1

Location: C SW SW Sec. 9 Twp. 32 Rge. 8 (E) (W) W

County Harper Total Depth 4369 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Smith was instructed to plug the well as follows:

211' of 8 p/8" surface pipe circulated with 175 sacks cement.

4363' of 5 1/2" long string cemented with 100 sacks. Sanded to

4360' cemented with 5 sacks. Fill hole to 200', 10' rock bridge,

cement with 20 sacks. Fill hole to 40', 10' rock bridge,

cement with 10 sacks.

Very truly yours,

Arlie Elving
 Conservation Division Agent