

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-007-21,618-00-00

LEASE NAME Lewis

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #1

SPOT LOCATION S 1/2 - NE

LEASE OPERATOR Attica Gas Venture

SEC. 35 TWP. 34 RGE. 11 (E) or (W)

ADDRESS 123 North Main, Attica, KS 67009

COUNTY Barber

Date Well Completed 8-10-83

PHONE # (316) 254-7222 OPERATORS LICENSE NO. 5039

Plugging Commenced _____

Character of Well D & A
 (Oil, Gas, D&A SWD, Input, Water Supply Well)

Plugging Completed _____

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City District #1

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Stalnaker Depth to top 3909 bottom 3999 T.D. 4020

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Stalnaker	Gas & Water	Surface	88'	13 3/8"		-0-
Mississippi	Oil - Gas & Water	Surface	329	8 5/8"		-0-
		Surface	4699	4 1/2"		3075'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.
Pumped 50 sax Class "A" Common - 2% gel + 3% CaCl from 3914' to 3850' stop plug @ 3850' - water from 3850' - from surface to 545' (starting @ 545 & up) 2 hulls - 10 gel - 50 cement 10 gel - 1 hull - wooden plug - 125 cement - used 60:40 Poz mix + 6% gel on second plug

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hays Well Service License No. _____
 Address Attica, KS

RECEIVED
 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Harper, ss.

AUG 22 1985
 8-22-85

Carl Durr (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carl Durr
 (Address) 123 North Main Attica, Ks. 67009

SUBSCRIBED AND SWORN TO before me this 20th day of August, 1985

MARILYN DOWNING
 NOTARY PUBLIC
 STATE OF KANSAS
 My Appt. Exp. 10-4-85

Marilyn Downing
 Notary Public

My Commission expires: