

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD  
OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging of formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission,  
800 Bitting Building  
Wichita, Kansas

Barber County, Sec. 12 Twp. 30 Rge. 5 (E) W. (W)  
C W 1/2 NW SW

NORTH



Locate well correctly on above  
Section Plat

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines  
Lease Owner Patton Drilling Company  
Lease Name W. M. Hoss Well No. 1  
Office Address Box 7 Hillside Sta. Wichita, Kans.  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole  
Date, well completed December 20, 1939  
Application for plugging filed " 1939  
Application for plugging approved " 1939  
Plugging Commenced " 1939  
Plugging Completed " 1939  
Reason for abandonment of well or producing formation Dry Hole  
If a producing well is abandoned, date of last production 1939  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation Depth to top Bottom Total Depth of Well 4760 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole was filled to 120 feet with heavy Rotary mud. Plug was set and two feet of rock put on top, four kegs of earth and 20 sacks of cement was put in filling hole to 100 ft., or 15 ft. inside of surface pipe. The hole was then filled with mud to 18 ft. where plug was set and rock, 4 kegs of earth and 10 sacks of cement were used filling hole to bottom of cellar. The 15" surface pipe was then cut off at the bottom of the cellar.

PLUGGING  
FILE SEC. 12-30-154  
BOOK PAGE 88 LINE 33

DEC 22 1939  
STATE CORP. COMM.  
CONSERV. DIV.  
12-22-39

(If additional description is necessary use BACK of this sheet)

Correspondence regarding this well should be addressed to Patton Drilling Company  
Address Box 7 Hillside Station Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
R. C. Patton (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. C. Patton

Box 7 Hillside Sta. Wichita, Kans.  
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of December, 1939

My commission expires April 12, 1943

Gaulita Thompson  
Notary Public

PATTON DRILLING COMPANY  
No. 1 Hoss

Sec. 12, Twp. 30S, Rge. 15W  
C W $\frac{1}{2}$  NW SW

Comm. Date: November 20, 1939  
Comp. Date: December 20, 1939


Potential: D & A

Casing Record:  
16" 115

shale	15
sand	40
shale & shells	70
sand	390
sand & red rock	645
lime	665
lime & shale	790
shale & shells	1090
lime broken	1125
lime	1132
salt	1175
shale	1260
shale & shells	1715
shale	1735
gyp lime	1770
shale	1835
lime	1985
lime broken	2135
lime	2175
shale & lime	2300
shale & shells	2325
lime	2415
shale	2470
lime & shale	2515
lime	2565
shale	2685
shale & lime	2770
shale & broken lime	2825
shale & lime	2950
shale	2975
lime	3000
lime broken	3150
lime	3195
lime broken	3270
lime	3445
lime broken	3540
lime	3635
lime broken	3665
lime	3720
shale	3750
shale & lime	3830
sand	3845
lime & shale	3920
lime	4325
lime broken	4355
lime	4460
chert & lime	4515
lime	4555
lime broken	4595
lime	4725
lime & chert	4760 T.D.

Sample Tops

Top Lansing	3905'
Top Simpson	4520'
Top Arbuckle	4610'



I, R. C. PATTON, do hereby certify that the above and foregoing is a true and correct copy of the log of Patton Drilling Company, No. 1 Hoss well, located in Section 12, Twp. 30S, Rge. 15W, Barber County, Kansas

R. C. Patton

Subscribed and sworn to before me, a Notary Public, this 21 day of December 1939

Barbara Thompson  
Notary Public

My commission expires: April 12, 1943

